Item 3-4 Drawing D-106, Sheet 11 of 62 - Nitrogen Removal Building - Demolition Sections

Add the following to the Demolition Plan:

## NOTES:

1. Sand has not been tested for hazardous materials. The Owner is not aware of any hazardous materials associated with the media. Media shall be disposed of at the RI Central Landfill as non-contract municipal solid waste. Contractor shall follow Rhode Island Resource Recovery Corporation (RIRRC) testing requirements which may include RCRA8 total metals, TCLP Metals for 20x Rule exceedances, pH, and flashpoint. The bacteria content does not require any special testing. The sampling required would likely be one sample based on the anticipated volume.

## Bidding Period Questions & Responses

The following responses/clarifications are based on questions raised during the bidding period

- 1. Drawing C- (light, medium, heavy) and where can the resulting sludge/solids be disposed of legally?
- 2. Will the Town drain and empty each tank (Primaries and Thickener tanks) prior to demolition?
- 3. Should the existing media (sand and gravel) to be considered hazardous waste for disposal purposes? If so, what level of hazardous waste should be considered?

- 4. Per RI state law, please confirm all mechanical work required to be performed by RI licensed contractors?
- 5. Drawing E-103 shows installing CU-1 as part of Bid Alt #3. However, E-702 shows CU-1 as part of Bid Alt #2. Please Clarify.